

ADDENDUM # 2

TO THE DRAWINGS AND SPECIFICATIONS FOR:

137th AVE CIRCLE ROADWAY AND DRAINAGE
IMPROVEMENTS (2016-153)

PREPARED FOR: CITY OF MADEIRA BEACH

DATED: MARCH 28, 2018

PREPARED BY: DEUEL & ASSOCIATES
565 S. HERCULES AVENUE
CLEARWATER, FL 33764
PHONE: (727) 822-4151
FAX: (727) 821-7255

THIS ADDENDUM #1 IS ISSUED TO ANSWER CONTRACTOR QUESTIONS.

Contractor questions with responses:

1. QUESTION: Plan sheet 3 shows the majority of 137th Ave Circle, Plymouth Street and Salem St to have 1" milling and resurfacing. Plan sheet 4 calls for these streets to have pervious concrete.

RESPONSE: On Plan sheet 3 the legend are swapped, the removal of asphalt and curb are majority 137th Ave-Cir., Plymouth and Salem Street to be replaced with Pervious Concrete. The Milling and Resurfacing is at the entrance to 137th Ave-Cir and part of 137th.

2. QUESTION: Pay item 4.3, Restoration of Adjacent Asphalt, 5,639 SY, where is this quantity located?

RESPONSE: The quantity is located around the entrance parking lots and at the Church lot. This is indicated on Plan sheet 4 outlining these areas. The intent is to have positive drainage from the surrounding parking areas. Therefore may not use all of this quantity.